

Bill of Quantity

Name of the work:-		फुलवडीयाको जियाउलको घर बाटोमा आर.सि.सि. ढलान ।					
Name of the project/place:-		खडक नगरपालिकाको कार्यालय, कल्यानपुर, सप्तरी, मधेश प्रदेश, नेपाल					
I. No.	Descreption of Project	Unit	Quantity	Rate in figure	Rate in word	Amount	Remarks
1	Site clearance work	M <sup>2</sup>	124.05				
2	Roadway Excavation & spreading work	M <sup>3</sup>	27.00				
3	Graveling work for sub base	M <sup>3</sup>	124.05				
4	PCC 1:2:4 work for RCC .	M <sup>3</sup>	18.61				
5	TMT steel bar for Reinforcement work (10 mm dia ) .	kg	890.58				
6	Form work	M <sup>2</sup>	16.91				
7	Steel Hording board	Job	1.00				
8	Lab Test (as per instruction of engineer .)	Job	1.00				
Total Amount Rs							
Vat 13% Rs							
Gr.Total Amount Rs							

Net Total Amount in Words:-

Contractors Name:-

PAN/VAT no

Address:-

Signature:-

Stamp

Date:-

Authorised Name:-